



Included:

- 2 each 10-24 screws (for Form 8 conduit bodies)
- 2 each 8-32 screws (for Mark 9 conduit bodies)

This part is for use on Form 8, Mark 9 and Standard 3/4" conduit bodies

SPECIFICATIONS:	
HOUSING MATERIAL	GLASS FILLED PBT
RECEPTACLE HOUSING:	NICKEL PLATED BRASS
RECEPTACLE INSERT:	POLYAMIDE
RECEPTACLE CONTACTS:	GOLD PLATED COPPER ALLOY
OPERATING VOLTAGE:	40V
OPERATING CURRENT:	4A
OPERATING TEMPERATURE	-40°C - +70°C

PROPRIETARY AND CONFIDENTIAL
THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF MENCOM CORPORATION. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF MENCOM CORPORATION IS PROHIBITED.

UNLESS OTHERWISE SPECIFIED: DIMENSIONS ARE IN INCHES AND [MM]	DRAWN BY	ADM	MENCOM CORPORATION	
	DRAWN DATE	09/22/2016		
	CHECKED BY			
	CHECK DATE			
MATERIAL	COMMENTS:		TITLE: 4 POL TERM BLK PLUG	
FINISH			SIZE B	DWG. NO. FFDC-2-4FR-CA
DO NOT SCALE DRAWING			SCALE: 1:1	WEIGHT:
			SHEET 1 OF 1	

A